

MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 22nd—24th July 1907.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, Mysore City Improvement Trust Board, up to 12th August 1907, for drainage and other works to be done in Blocks Nos. 2, 28, 34 and 35 of No. III Drainage Area. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1908.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the office of the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for drainage and other works to be done in Block Nos. 2, 28, 34 and 35 of III Drainage Area;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage and other works to be done in a portion of No. III Drainage Area of the Mysore City, Blocks Nos. 2, 28, 34 and 35.

No.	Items of work.	Per	Approximate quantity.
1.	Earthwork, excavation for constructing drains of semi-peg top section, silt-traps, flushing tanks, etc., ordinary soil ...	C. yd.	1,253
2.	Do do other soil ...	Do	552
3.	Cement concrete including rendering the surface of the drains, silt traps, etc., smooth with cement ...	C. ft.	33,863
4.	Machine-ground surki mortar concrete for constructing flush tanks and latrines ...	Do	2,212
5.	Cement plastering $\frac{1}{4}$ " thick ...	Sqr.	5.05
6.	Cement plastering $\frac{1}{2}$ " thick ...	Do	32.60
7.	Burnt stone slabs 3" thick, dressed with two line and groove cut, set in mortar over silt-traps ...	S. ft.	712
8.	Burnt stone slab coping $4\frac{1}{2}$ " thick dressed with two line set in mortar for flushing tanks ...	Do	109
9.	Armoured surki concrete slab 3" thick, including cornice, for roofing latrines ...	Do	269
10.	Constructing parapets with 6" thick burnt stone slabs with two-line dressing fixed in concrete and joined in mortar ...	Do	3,948
11.	Coverings to drains at the crossings of roads and conservancy lanes either with armoured concrete slab or 6" thick burnt stone slabs dressed at sides set in mortar ...	Do	5,165
12.	Removing the slab stones of existing V-shaped drains ...	R. ft.	18,319
13.	Do do box drains ...	Do	2,616
14.	Resetting the slab stones, pointing the joints with mortar ...	Do	20,935
15.	Earthwork, cutting and filling for grading roads and conservancy lanes ...	C. yd.	3,750
16.	Forming and gravelling the roads 3" thick, including collecting, carting and consolidating ...	S. yd.	9,420
17.	Earthwork, excavation for constructing under-drains in damp places ...	C. yd.	5,418
18.	Refilling with earth and tamping do ...	Do	3,386
19.	Collecting, carting and filling with road metal do ...	Do	2,032
20.	Turfing do do ...	S. yd.	5,080

Machinery for grinding mortar will be made available, the tenderer bearing the charges for the preparation of the mortar.

Dated 22nd—24th July 1907.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, Mysore City Improvement Trust Board, up to 12th August 1907 for drainage and other works to be done in a portion of No. 3 Drainage Area, Blocks Nos. 1, 33, 32 and 53. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1908.

2. The plans, detailed estimate and conditions may be seen at the office of the Chairman between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the office of the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for drainage and other works to be done in a portion of No. 3 Drainage Area," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Statement showing the quantity of drainage and other works to be done in a portion of No. 3 Drainage Area of the Mysore City, Blocks Nos. 1, 33, 32 and 53.

No.	Items of work.	Per	Approximate quantity.
1.	Earthwork, excavation for constructing drains of semi. peg top section, silt-traps, flush tanks, etc., ordinary soil	C. yd.	1,025
2.	Do do do other soil	"	448
3.	Cement concrete including rendering the surface of the drains, silt-traps, etc., smooth with cement	C. ft.	27,179
4.	Machine-ground surki mortar concrete for constructing flush tanks and latrines	"	2,152
5.	Cement plastering $\frac{1}{4}$ " thick	Sqr.	0.04
6.	Cement plastering $\frac{1}{2}$ " thick	"	32.60
7.	Burnt stone slabs 3" thick dressed with two line and groove cut, set in mortar over silt-traps	Sq. ft.	528
8.	Burnt stone slab coping $4\frac{1}{2}$ " thick dressed with two line set in mortar for flushing tanks	"	93
9.	Armoured surki concrete slab 3" thick, including cornice, for roofing latrines	"	269
10.	Constructing parapet with 6" thick burnt stone slabs with two line-dressing, fixed in concrete and joined in mortar	"	2,324
11.	Coverings to drains at the crossings of roads and conservancy lanes either with armoured concrete slab or 6" thick burnt stone slabs dressed at sides set in mortar	"	7,125
12.	Removing the slab stones of existing V-shaped drains	R. ft.	15,631
13.	Do do box drains	"	2,233
14.	Resetting the slab stones, pointing the joints with mortar	"	17,864
15.	Earthwork, cutting and filling for grading roads and conservancy lanes	C. yd.	3,395
16.	Forming and gravelling the roads 3" thick, including collecting, carting and consolidating	S yd.	7,755

Machinery for grinding mortar will be made available, the tenderer, bearing the charges for the preparation of the mortar.

D. SITARAMA RAO,
Chairman.